

CERTIFIED LAND CORNER RESTORATION

Index No. B-1

State of Wisconsin

County of Oneida } ss.

History of original corner establishment:
No records of any previous survey.


I, Phillip J. Hansen, do hereby certify that on the 5th day of April, 19 79, I found ~~existence of the~~ corner of Section 1 & 6

of Section 1 & 6, Township 35, North, Range 10 & 11 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Description of corner evidence found:
No evidence of any corner recovered. Corner established by traverse and computation. Ran traverse from 1/4 corner between section 1 and 6 to section corner 31, 36, 1 and 6. Computed distance of 2483.915 at bearing N 0° 07' 46" W. Set N 1/16 by proportional distance based on original survey. N 1/16 set S 0° 07' 46" E, 1172.065' from section corner and N 0° 07' 46" W 1355.85' from 1/4 corner.

Resident witnesses:


Glen Barker
Jim Claflin
Herb Wagoner



Description of monument and accessories I established to perpetuate the original location of this corner.
Drove a 1-1/2" x 14" iron pipe on the west edge of old highway 26 south, 6" below the surface for true corner.

Set a 1 1/2" iron pipe with 2" brass cap, 40 ft. west for witness corner.
Monument projects 18" above ground. Cap stamped:
Marked NBT's - Maple 7" S65°E 40.20 feet, scribed 1/16 BT. T35N R10E R11E
Maple 6" N50°E 66.78 feet, scribed 1/16 BT. N 1/16 1+6 W.C.
Measurements & bearings from true corner.

E-40'
CPI-1979



O = Corner monument restored.

Dated at Rhineland, Wis., this 24th day of April, 19 79.

Signature Phillip J. Hansen Title Registered Land Surveyor Registration No. S-498
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida, I hereby certify that the within instrument was filed in this office for record on the 14th day of May, 19 79 at 3:00 o'clock P. M.

By Doris Venage Fuchs Deputy
(Register of Deeds)

35/0013000