

CERTIFIED LAND CORNER RESTORATION

Index No. **B-19**

State of Wisconsin

County of Oneida } ss.

I Phillip T. Hansen, do hereby certify that on the 21st day of May, 1976, I found evidence of the NC 1/16 corner of Section 2 Township 35, North, Range 10 East, Fourth Principal Meridian,



as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

Glen Barker

Jim Clafflin

Herb Wagoner



○ = Corner monument restored.

History of original corner establishment:
Original corner established by B.F. Dorr, County Surveyor, in 1896.

H.C. Lawrence, registered Land Surveyor, recovered his post in 1954. Found stump of his Maple 12" S 36 1/2" E 10 1/2 lks. Scribe marks visible.
Set new post and marked NBTs - Hemlock 7" S 28° E 32 lks.
Cedar (dead) 10" S 10° E 37 lks.

Description of corner evidence found:

Recovered 6" cedar post, squared and scribed NC 1/16 S2, NC 1/16 S2, post had rotted off at ground level and fell down. Recovered point in ground.
Recovered OBT - Maple 12" S 36 1/2" E 10.5 lks, now a decayed stump.
Hemlock 7" (8") S 28° E 32 lks, scribed NC 1/16.
Dead Cedar 10" S 10° E 37 lks, scribed 1/16 BT.

Description of monument and accessories I established to perpetuate the original location of this corner.
Replaced 6" cedar post with 1 1/2" iron pipe with 2" brass cap stamped.
Monument projects 2 1/2" above ground.
NBT - Juglar 8" N 68° W 36 lks, scribed 1/16 BT.
Monument and BTs painted blue.

498
T35N R10E
NC 1/16 S 2
CPT-1976

Dated at Princeton, Wis., this 5th day of August, 1976.

Signature Phillip T. Hansen Title Registered Land Surveyor Registration No. 5-498
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida.
I hereby certify that the within instrument was filed in this office for record on the 22nd day of September, 1976 at 1:08 o'clock P. M.

Terrie Neugebauer
(Register of Deeds)

By Terrie Neugebauer Deputy

0200200158