



CERTIFIED LAND CORNER RESTORATION

Index No. **G**

State of Wisconsin } ss.  
 County of Oneida

I Phillip T. Hansen do hereby certify that on the 9th day of October, 19 78, I found evidence of the C 1/4 corner of Section 11 Township 35 North, Range 10 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:  
Jim Clafflin  
Herb Wagoner



○ = Corner monument restored.

History of original corner establishment:

Corner established by N. Loftus, Ripco Surveyor.  
 Set 2" iron pipe with 3" brass cap.  
 Marked BT's - Aspen 6" S39°W 47.25 links  
 Maple 9" S11°E 27.0 links  
 B.Spruce 7" S85°W, 48.25 links

Description of corner evidence found:

Recovered Ripco's 2" iron pipe with 3" square brass cap in excellent condition.  
 Monument projects 2 1/2 ft. Cap stamped:  
 Recovered Aspen 6" S39°W 47.25 links, scribing legible.  
 No evidence of other BT's.

Description of monument and accessories I established to perpetuate the original location of this corner.  
 As monument was recovered in good condition, it was left as recovered.

Marked NBT's -  
 Maple 6" N3°W 71.6 links  
 W. Birch 7" S66°E 61.2 links  
 both scribed 1/16 BT

Dated at Rhinelander, Wis., this 18th day of October

Signature: Phillip T. Hansen Title: Registered Land Surveyor Registration No. S  
 (County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida  
 Instrument was filed in this office for record on the 6th day of November at 10:00 o'clock A. M.

Doris George Fuchs  
 (Register of Deeds)

By: \_\_\_\_\_ Deputy