

CERTIFIED LAND CORNER RESTORATION


Index No. G-6

State of Wisconsin

County of Oneida } ss.

I, Phillip T. Hansen, do hereby certify that on the 21st day of May, 1975, I found evidence of the WC-1/16 corner of Section 8 Township 35 North, Range 11E, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:



History of original corner establishment:

Corner established by H.C. Lawrence, Registered Land Surveyor, during his retracement survey in 1954. From established 1/4 corner between Section 7 and 8 he ran N84°50'E on random line, 43.92 chains to intersect N-S-1/4 line, 1.32 chains north of recovered C-1/4 corner. Set WC-1/16 corner at 21.96 chains equidistant, 66 links south of random line. Corrected bearing N86°33'E.
 Established NBT's: Maple 14" N48°E 60-1/2 links
 Sugar 10" S88°W 38-1/2 links

Description of corner evidence found:


Recovered 4" hemlock post, squared and scribed WC-1/16 S8, WC-1/16 S8 in good condition. Also a 1-1/2" iron pipe was set up beside it.
 Recovered OBT's: Sugar 10" S88°W 38.5 links blown over and decayed, scribing visible
 Red maple 14"(15) N48°E 60.5 links scribed WC-1/16BT

Description of monument and accessories I established to perpetuate the original location of this corner.

Replaced 4" hemlock post with 1-1/2" OD iron pipe w/2" brass cap stamped - S498 T35N R11E

Established NBT: White birch 9" S68°E 58.7 links scribed 1/16BT

WC-1/16 S8
 CPI-1975



○ = Corner monument restored.

Dated at Rhineland, Wis. this 6th day of June, 1975.

Signature Phillip T. Hansen Title Registered Land Surveyor Registration No. S-498
 (County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida I hereby certify that the within instrument was filed in this office for record on the 1st day of October, 1975 at 3:00 o'clock P.M.

Dorinda George Kuehn
 (Register of Deeds)

By: _____ Deputy

3511082030