



CERTIFIED LAND CORNER RESTORATION

Index No. R-10

State of Wisconsin }  
County of Oneida } ss.

I Phillip T. Hansen, do hereby certify that on the 22nd day of May, 1978, I ~~found~~ restored the W 1/16 corner of Section 21 & 28 Township 35, North, Range 11 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:  
Glen Barker  
Jim Clafflin  
Herb Wagoner



○ = Corner monument restored.

History of original corner establishment:  
**No records of any previous survey.**

Description of corner evidence found:  
**No evidence of any monument recovered.**  
Corner established by traverse and computation. Ran traverse between previously established 1/4 corner and section corner 20, 21, 28 & 29. Computed distance 2638.677 feet at bearing N 88° 01' 13" W. Set W 1/16 at 1319.339 feet intermediate.

Description of monument and accessories I established to perpetuate the original location of this corner.  
Set 1 1/2" iron pipe with 2" brass cap, stamped:  
Monument projects 24" above ground.  
Marked NBT's -  
Maple 6" N79°E, 35.85 feet  
White Birch 6" North 21.55 feet  
scribed 1/16 BT.  
S498  
T35N R11E  
W 1/16 S 21  
S 21  
CPI-1978

Dated at Rhinelander, Wis., this 5th day of June, 1978  
Signature: Phillip T. Hansen Title: Registered Land Surveyor Registration No. S-498  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)  
Office of Register of Deeds, County of Oneida  
Instrument was filed in this office for record on the 13th day of June, 1978 at 2:30 o'clock P. M.  
Dawn Deage Tuelke (Register of Deeds)  
By: Joseph M. Barner Deputy

3511210030