



CERTIFIED LAND CORNER RESTORATION

Index No. P12

State of Wisconsin }
County of Oneida } ss.

I Phillip T. Hansen, do hereby certify that on the 28th day of June, 19 78, I ~~have~~ restored established the EC 1/16 corner of Section 21 Township 35, North, Range 11 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:
Glen Barker
Jim Claflin
Herb Wagoner
J. Masbaum



○ = Corner monument restored.

History of original corner establishment:
No records of any previous survey.

Description of corner evidence found:
No evidence of any corner recovered.
Corner established by traverse and computations from previously established E 1/4 and C 1/4 corner. Computed distance is 2685.288 feet at bearing S 89° 16' 10" E.
Set EC 1/16 corner at 1342.644 feet intermediate.

Description of monument and accessories I established to perpetuate the original location of this corner.
Set 1 1/2" iron pipe with 2" brass cap projecting 24" above ground. Cap stamped:
Marked NBT's
Maple 6" S37°W, 45.66 feet, scribed 1/16 BT.
Maple 7" S75°W, 54.11 feet, scribed 1/16 BT.
S498
T35N R11E
EC 1/16 S 21
CPI-1978

Dated at Rhineland, Wis., this 5th day of July, 19 78.

Signature Phillip T. Hansen Title Registered Land Surveyor Registration No. S-498
(County Surveyor, Registered Land Surveyor, or other duly authorized official)
Office of Register of Deeds, County of Oneida
at 10:00 o'clock A. M. July day of July, 19 78.
I hereby certify that the within instrument was filed in this office for record on the 17th day of July, 19 78.

Doris Savage Kuehn
(Register of Deeds)

By Doris Savage Kuehn Deputy

3511212010