

CERTIFIED LAND CORNER RESTORATION

Index No. **S-22**

State of Wisconsin } ss.  
 County of Oneida }


I Phillip T. Hansen do hereby certify that on the 15th day of November, 1976, I found evidence of the 1/16 corner of Section 25 Township 25, North, Range 11 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

Glen Parker

Jim Clafflin

Herb Larson




History of original corner establishment:  
 H.C. Lawrence, Registered Land Surveyor, recovered a point of old strike 26 links west of where an old fence line (H-C) ends and runs west. Set post at intersection of old H-C and west fence line. No record of any corner set or RT marked.

Description of corner evidence found:

Recovered a 4" cedar post, squared and scribed to 1/16 x 25, in fair condition. Also found a piece of old cedar post lying on ground. Corner sets at intersection of old and fence line south.  
 Recovered OPMS - Sugar 10W, 58° to 38.2 links, scribed to 1/16 x 25.  
 Sugar 4 SW, 40° to 37.7 links, scribed to 1/16 x 25, visible.  
 Sugar 10W, 100° to 10 links, scribed to 1/16 x 25.

Description of monument and accessories I established to perpetuate the original location of this corner.

Replaced 4" cedar post with 1" iron pipe with 2" brass cap screw set monument projects 4" above ground.  
 OPMS - Sugar 10W, 58° to 38.2 links, scribed 1/16 x 25.  
 Corner sets in the 4" corner of an old field.  
 10350 1/16  
 1/16 x 25  
 011-1976



Dated at Oneida, Wis., this 1st day of December, 1976.

Signature Phillip T. Hansen Title Registered Land Surveyor Registration No. 493  
 (County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida  
 I hereby certify that the within instrument was filed in this office for record on the 9th day of December, 1976 at 2:02 o'clock P.M.

Barbara Savage Tuck  
 (Register of Deeds)

By Joseph M. Brown Deputy

3511253030