

CERTIFIED LAND CORNER RESTORATION

Index No. X-8



State of Wisconsin

County of Oneida

ss.

I Phillip T. Hansen, do hereby certify that on the 15th day of November, 1978, I found established the EC 1/16 corner of Section 32 Township 35, North, Range 11 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:
Glen Barker
Jim Clafflin
Herb Wagoner



○ = Corner monument restored.

History of original corner establishment:
No records of any previous survey.

Description of corner evidence found:

No evidence of any corner recovered. Corner established by traverse and computation during resurvey of section 32. Computed distance from C 1/4 corner to East 1/4 corner is 2689.953 feet at bearing S 88° 32' 31" E.
Set EC 1/16 at 1344.977 feet intermediate. Corner sets approximately 300 feet south of Pedro Creek.

Description of monument and accessories I established to perpetuate the original location of this corner.
Set 1 1/2" iron pipe with 2" brass cap projecting 12" above ground, cap stamped:
No RT's available, all river bottom and alders.

Set two 1 1/2" x 5' iron pipes for witness monuments.
#1 - due south 18 feet
#2 - due west 20 feet
both project 24" above ground

S498
T35N R11E
S 32
EC 1/16
CPI-1978

Dated at Rhineland, Wis., this 4th day of December, 1978

Signature: Phillip T. Hansen Title: Registered Land Surveyor Registration No. S-498
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida
Instrument was filed in this office for record on the 10th day of January, 1979
at 1:00 o'clock P.M.

Terrie Wagoner Kuehn
(Register of Deeds)

By: _____ Deputy

351132 2010