

CERTIFIED LAND CORNER RESTORATION

Index No. W-7

State of Wisconsin }
County of Oneida } ss.

History of original corner establishment:
No records of any previous survey.


I Phillip T. Hansen, do hereby certify that on the 15th day established December, 1978, I ~~found~~ restored the NC 1/16 corner of Section 32 Township 35 North, Range 11 East, Fourth Principal Meridian,

as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.


Resident witnesses:

Glen Barker

Jim Clafflin



T35N R11E



○ = Corner monument restored.

Description of corner evidence found:

No evidence of any corner recovered. Corner established by traverse and computation while running subdivision of section 32. Computed distance from established N 1/4 corner to C 1/4 at 2615.617 feet at bearing S 4° 24' 15" W.
Set NC 1/16 at 1307.809 feet intermediate.

Description of monument and accessories I established to perpetuate the original location of this corner.

Set 1 1/2" iron pipe with 2" brass cap, projecting 12" above ground. Cap stamped:

Corner sets in an alder marsh. No trees available for BT's.

Set two 1 1/2" x 4' iron pipes for witness monuments.

#1 - sets south 15'

#2 - sets east 12'

both project 18" above ground.

S498
T35N R11E
NC 1/16 S 32
CPI-1978

Dated at Rhineland, Wis., this 18th day of December, 19 78

Signature Phillip T. Hansen Title Registered Land Surveyor Registration No. S-498
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida
at 1:15 o'clock P. M. 25th day of January, 19 79
I hereby certify that the within instrument was filed in this office for record on the

Doris Leverage Kuehn
(Register of Deeds)

By Doris Leverage Kuehn Deputy

3511323020