

CERTIFIED LAND CORNER RESTORATION

Index No. W-11

State of Wisconsin

County of Oneida } ss.

History of original corner establishment:  
No records of any previous surveys.


I Phillip T. Hansen, do hereby certify that on the 6th day of September, 1978, I ~~restored~~ re-established the NC 1/16 corner of Section 33 Township 35, North, Range 11 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Description of corner evidence found:  
No evidence of any corner recovered.

Corner established by traverse and computation, C 1/4 corner established from E-W and N-S 1/4 lines. Computed distance from N 1/4 corner to C 1/4 is 2474.738 feet at bearing S 1° 11' 01" E. Set NC 1/16 at 1237.369 feet intermediate.

Resident witnesses:


- Glen Barker
- Jim Clafin
- Herb Wagoner



Description of monument and accessories I established to perpetuate the original location of this corner.

- Set 1 1/2" iron pipe with 2" brass cap, stamped: Monument projects 18" above ground.
- No trees suitable for BT's -
- Set two 1 1/2" x 5' iron pipes for witness monument.
- # 1 - North 20'
- # 2 - East 15'

S498  
T35N R11E  
NC 1/16 S 1/33  
CPI-1978



○ = Corner monument restored.

Dated at Rhinelander, Wis., this 11th day of September, 1978.

Signature Phillip T. Hansen Title Registered Land Surveyor Registration No. S-498  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida. I hereby certify that the within instrument was filed in this office for record on the 25th day of September, 1978 at 2:50 o'clock P. M.

Dorcas Venega Kuehn  
(Register of Deeds)

By: \_\_\_\_\_ Deputy

3511333020