

CERTIFIED LAND CORNER RESTORATION

Index No. P-21

State of Wisconsin }  
County of Oneida } ss.

I Jerome N. Kraemer, do hereby  
certify that on the 5th day  
of May, 1978, I found  
evidence of the West one-quarter  
corner of Section 24  
Township 36, North, Range  
7 East, Fourth Principal Meridian,

as described hereon; and that from this evidence  
I established a new monument and accessories  
as described hereon to perpetuate the original  
location of this corner.

Resident witnesses:

None

This is a copy of a copy. The

ORIGINAL CORNER BE LOCATED.

Monument Restored 3/10/95

Section 24, T36N, R7E

4/14/98

Distance to Vaughan's  
stump should be

57.5 links (37.95')

Confirmed by Jim

Rein wilderness Survey

*JD*

○ = Corner monument restored.

History of original corner establishment:

Original corner post established by Alex Anderson in November, 1862

Original Bearing Trees:

Y. Pine 9" S86°W, 15 links (9.90 feet)  
Aspen 13" N67°E, 13 links (6.60 feet)

Description of corner evidence found:

D. H. Vaughan's notes from December 6, 1890 witnessed the one-quarter corner  
with the South rail of Soo Railroad, Northeast 3 links (1.98 feet) and  
Y. Pine Stump bearing S41°E, 87.12 links (57.50 feet)

Description of monument and accessories I established to perpetuate the original location of this corner.

Set Oneida County Survey Marker (Cast aluminum Bernsen Monument) 3-1/2" dia,  
2" inside diameter and 30" long by cross chaining in 1.98 feet from South rail  
of Soo Railroad and 57.50 feet from scribed stump, as recorded in Vaughan's  
notes 1890.

Set monument 12" below surface, made bearing trees;  
Set P.K. nail in 9" Poplar, N15°W, 49.17 feet;  
Set P.K. nail in 6" Oak, N85°E, 57.85 feet;  
Set P.K. nail in 9" Maple S7°E, 56.25 feet.

Scribed bearing trees.

Dated at Minocqua, Wis., this 27th day of December, 1978

Signature [Signature] Title Registered Land Surveyor Registration No. 1448  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of \_\_\_\_\_, I hereby certify that the within  
instrument was filed in this office for record on the \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_  
at \_\_\_\_\_ o'clock \_\_\_\_\_ M.

(Register of Deeds)

By: \_\_\_\_\_ Deputy

3607232000