

CERTIFIED LAND CORNER RESTORATION



Index No. **P-12**

State of Wisconsin } ss.
 County of Oneida }

I Philip T. Hansen do hereby certify that on the 9th day of April, 1976, I found evidence of the WC 1/16 corner of Section 21 Township 36 East, Range 9 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

- Glen Barker
- Jim Clafin
- Herb Wagoner



O = Corner monument restored.

History of original corner establishment: Corner established by Ripco Surveyors, Goddard and crew, in 1961. From recovered 1/4 corner between sections 20-21, ran 88° 30' mag. 81.16 chains. Closed out 16 lks south of W 1/4 corner in road. set WC 1/16 corner at 60.8079 chains, 11.95 lks north in road. set pin in road for corner. set reference pipe 25 lks north.

Description of corner evidence found:
 Recovered RR spike in North Lane of River Bend Road. Recovered a 1" iron pipe with aluminum cap 25 lks north, cap stamped.
 No BT notes on record and none in evidence.
 Corner sets 7.547 chains East of Felician River.
 Cor. 25 lks south
 O-1/16
 Ripco

Description of monument and accessories I established to perpetuate the original location of this corner.
 As RR spike and witness monument were in excellent condition, we left them in place.
 Added T36N R9E to stamping on aluminum cap.
 No record or evidence of BTs. Made NBO - Hi line Pole 3609-21R21-576° E 179.8 lks and Hi line Pole 3609-21R20 278.0 lks, S 79° ..
 Measurements and bearings from true corner to center of Hi line poles.
 Witness Monument painted blue.

Dated at Rainelander, Wis., this 19th day of July, 1976.
 Signature: *Philip T. Hansen* Title: Registered Land Surveyor Registration No. 3498
 (County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida
 Instrument was filed in this office for record on the 23rd day of July, 1976, at 1:20 o'clock P.M.
 Signature: *David George Kuehn*
 (Register of Deeds)

By: _____ Deputy

3609 21 2016