

CERTIFIED LAND CORNER RESTORATION

State of Wisconsin }
 County of Oneida } ss.

I Philip T. Hansen, do hereby certify that on the 25th day of August, 1975, I found evidence of the Section corner of Sec. 19, 30, 25, 24 Township 36 North, Range 9 and 10 east, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:
 Original corner established by Hiram C. Fellows, Gov. Deputy Surveyor in 1859, from which Tamarack 8" bears S 60° W 10 lks, Y. Pine 8" bears N 50° W 30 lks, Fir 6" bears N 65° E 7 lks and Tamarack 8" bears S 35° E 22 lks.
 Corner reestablished by H.C. Lawrence, Registered Land Surveyor in 1947 during his re-tracement survey. Set 4" Tamarack post, squared and scribed from which Red pine 12" bears N 36° W 88 lks.

Description of corner evidence found:
 Recovered 1½" iron pipe set in old post hole with rock carron around it. Also a 4" Tamarack post squared and scribed laying on the ground, badly decayed, S 24 R 9 E - R 10 E only scribe marks visible
 Recovered OPT Red Pine 12" N 36° W 88 lks, scribed S 24 BT


Description of monument and accessories I established to perpetuate the location of this corner:

Replaced 1½" iron pipe with 2½" iron pipe with brass cap stamped
 NBT Jackpine 9" N 14° E 55.3 lks scribed SC BT

S 498
 T36N
 R S24 | 319 R
 9 S25 | S30 10
 E E
 CPI 1975



T 36 N R 10 E



● - Corner monument restored
 □ -

Residence witnesses Glen Barker and Jim Claflin

Dated at Rhineland Wisconsin, this 25th day of August, 1975

Signature Philip T. Hansen Title Reg. Land Surveyor
 (County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. S 498

Office of Register of Deeds County of Oneida

I hereby certify that the within instrument was filed in this office for record on the 14th day of October, 1975, and was filed in Book No. _____ Page No. _____ of County Records.

Signature Doris Verage Kuehn Title Register of Deeds

Township 36 North, Range 10 East, Section 19, Index No. _____, Page No. _____