

CERTIFIED LAND CORNER RESTORATION



Index No. R-3

State of Wisconsin

County of Oneida } ss.

I Phillip T. Hansen, do hereby certify that on the 16th day of August, 1979, I found ~~and~~ restored the Quarter corner of Section 19 and 30 Township 36, North, Range 10 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:
Glen Barker
Jim Claflin
Herb Wagoner



○ = Corner monument restored.

History of original corner establishment:

Original corner established by Wm. E. Dougherty, Deputy Surveyor, in 1863, from which Aspen 7" bears N61°W 10 links; Aspen 8" bears S42°E 4 links.

No records of any subsequent survey.

Description of corner evidence found:

No evidence of any corner recovered. Corner established by traverse and computation. Ran traverse from section corner 19, 20, 29 and 30 to section corner 19, 24, 25 and 30, total distance computed at 5450.103 feet at bearing S 79° 30' 49" W. Set 1/4 corner proportioned to original measurement. Corner sets S 79° 30' 49" W, 2687.852 feet from section corner 19, 20, 29, 30 and 2762.851' N 79° 30' 49" E of section corner 19, 24, 25, 30.

Description of monument and accessories I established to perpetuate the original location of this corner.

Set a 2-1/2" Berntsen A-1 Federal Monument projecting 18" - stamped:

- Marked NBT's -
- Black Spruce 10" N37°W 28.95', scribed 1/4 BT. T36N R10E
- Black Spruce 6" N66°W 38.39', scribed 1/4 BT. S 19
- White Birch 9" N52°E 21.80', scribed 1/4 BT. 1/4 S+30
- Black Spruce 4" S21°E 10.30', scribed 1/4 BT. S498-1979

Dated at Rhinelander, Wis., this 20th day of August, 1979

Signature Phillip T. Hansen Title Registered Land Surveyor Registration No. S-498
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida I hereby certify that the within instrument was filed in this office for record on the 27th day of August, 1979 at 100 o'clock P. M.

Thomas George Krul
(Register of Deeds)

By: _____ Deputy

0200190020