

CERTIFIED LAND CORNER RESTORATION

Index No. Q-3



State of Wisconsin

County of Oneida } ss.

History of original corner establishment:  
No records of any previous survey.

I Philip T. Hansen, do hereby certify that on the 15th day of August, 19 79, I ~~restored~~ restored the SC 1/16 corner of Section 19 Township 36, North, Range 10, East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:  
Glen Barker  
Jim Claflin  
Herb Wagoner



○ = Corner monument restored.

Description of corner evidence found:  
No evidence of any corner recovered.  
Corner established by traverse and computation. Ran traverse from N 1/4 to S 1/4 corner and from W 1/4 corner to E 1/4 corner to establish the C 1/4. Computed distance from C 1/4 to S 1/4 corner is 2649.303' at bearing S 20° 49' 20" W.  
Set SC 1/16 corner at 1324.652' intermediate.

Description of monument and accessories I established to perpetuate the original location of this corner.  
Set a 1-1/2" iron pipe with 2" brass cap, projecting 18", stamped:  
Marked NBT's - S498  
Tamarack 6" N6°W 23.45 feet, scribed 1/16 BT. T36N R10E  
Tamarack 5" S50°E 42.93 feet, scribed 1/16 BT. SC 1/16 S 19  
CPI-1979

Dated at Rhinelander, Wis., this 20th day of August, 19 79.

Signature Philip T. Hansen Title Registered Land Surveyor Registration No. S-498  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)  
Office of Register of Deeds, County of Oneida  
at 1:30 o'clock P. M. 27th day of August, 19 79.  
Philip T. Hansen (Register of Deeds)

By \_\_\_\_\_ Deputy

3610191020