

CERTIFIED LAND CORNER RESTORATION

Index No. P-7

State of Wisconsin

County of Oneida } ss.



I Phillip T. Hansen, do hereby certify that on the 3rd day of March, 1979, I found ~~the~~ the ~~original~~ original corner of Section 20 Township 36, North, Range 10 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

Glen Barker

Jim Clafflin

Herb Wagoner



○ = Corner monument restored.

History of original corner establishment:
No records of this corner having been established.

Description of corner evidence found:

No evidence of this corner recovered. Corner established by traverse and computation. Ran traverse connecting exterior corners of section. Computed the positions of 1/4 corners and distances and bearings between 1/4 corners. Computed location of C 1/4 corner is S 0° 31' 39" W 2665.284 feet from N 1/4 corner, S 89° 14' 33" W 2616.745' from E 1/4 corner, N 0° 21' 39" E 2557.642' of S 1/4 corner and N 89° 14' 33" E 2810.03' of W 1/4 corner.

Description of monument and accessories I established to perpetuate the original location of this corner.
Set 2 1/2" Berntsen A-1 Federal Monument, projecting 18" above ground, stamped:

- Marked NBT's -
- Jack Pine 7" S55°E 22.13 feet T36N R10E
- Jack Pine 10" N42°E 13.58 feet C 1/4 S 20
- Jack Pine 9" S50°W 11.08 feet S498-1979
- all scribed C 1/4 BT

Dated at Rhineland, Wis., this 8th day of May, 1979.

Signature Phillip T. Hansen Title Registered Land Surveyor Registration No. S-498
(County Surveyor, Registered Land Surveyor, or other duly authorized official)
Office of Register of Deeds, County of Oneida, I hereby certify that the within instrument was filed in this office for record on the 21st day of May, 1979 at 2:00 o'clock P. M.

Debra Verage Kuehn
(Register of Deeds)

By: _____ Deputy

3610202020