

CERTIFIED LAND CORNER RESTORATION

Index No. **Q-15**

State of Wisconsin }
 County of Oneida } ss.



I Phillip T. Hansen, do hereby certify that on the 19th day of May, 1976, I found evidence of the SG 1/16 corner of Section 22 Township 36, North, Range 10 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

Glen Barker

Jim Claffin

Herb Jagoner



○ = Corner monument restored.

History of original corner establishment: Original Corner established by J.H. Vaughan, County Surveyor, in 1910. Marked Tamarack 10" S 9° W 12 lks and Tamarack 10" S 9° W 12 lks.

Corner recovered by H.C. Lawrence, Registered Land Surveyor, in 1947. Found Vaughan's post and BTs. Set a new post, but no mention of any new BTs in notes.

Description of corner evidence found: Recovered Lawrence's 4" cedar post, squared and scribed 222 SG 1/16.

Recovered BT - Tamarack 10" N 24° E 17 lks, now a decayed stump, scribing 1/8 BT visible. Tamarack 10" S 9° W 12 lks, now a decayed mound.

Description of monument and accessories I established to perpetuate the original location of this corner. Replaced 4" cedar post with 1 1/2" iron pipe with 2" brass cap stamped.

Monument projects 18" above ground. 3498
 NBTs - Black Spruce 8" N 30° E 19.2 lks, scribed 1/16 BT. T36N R10E
 Black Spruce 8" S 11° W 19.1 lks, scribed 1/16 BT.

Placed rock cairn around base of monument. SG 1/16 S 122
 Monument and BTs painted blue. CPI-1976

Dated at Rhinelander, Wis., this 4th day of August, 1976

Signature Phillip T. Hansen Title Registered Land Surveyor Registration No. 3-498
 County Surveyor, Registered Land Surveyor, or other duly authorized official

Office of Register of Deeds, County of Oneida. I hereby certify that the within instrument was filed in this office for record on the 22nd day of September, 1976 at 1:00 o'clock P.M.

Debra Lorraine Fiehn
 (Register of Deeds)

By _____ Deputy

020122019