

CERTIFIED LAND CORNER RESTORATION

Index No. 0 - 3

State of Wisconsin

County of Oneida } ss.

I, Glen Barker, do hereby

certify that on the 12th day

of June 19 84, I have

established the SC 1/16

corner of Section 30

Township 36 North, Range

10 East, Fourth Principal Meridian,

as described hereon; and that from this evidence

I established a new monument and accessories



as described hereon to perpetuate the original

location of this corner.

Resident witnesses:

N. Spiess

H. Wagoner



○ = Corner monument restored.

History of original corner establishment:

No evidence of any previous corner.

Description of corner evidence found:

Total distance from 1/4 corner between sections 30 and 31 to C 1/4 Section 30 is 2689.43'.

Set SC 1/16 1344.72' intermediate.

Description of monument and accessories I established to perpetuate the original location of this corner.

Set a 1" iron pipe with 2" diameter alloy cap, stamped: Monument projects 18" above ground.

Marked NBTs:

White Pine 8" N47W 5.70'

Maple 8" N65E 11.96'

scribed 1/16 B.T.

S1682

T36N

SC 1/16 S 30

R10E

CPI - 1984

Dated at Rhinelander, Wis., this 8th day of August, 19 84

Signature: *Glen Barker* Title: Registered Land Surveyor Registration No. S1682

(County Surveyor, Registered Land Surveyor or other duly authorized official)

Office of Register of Deeds, County of Oneida, I hereby certify that the within instrument was filed in this office for record on the 10th day of December, 19 84 at 11:30 o'clock A.M.

Dona George Kuehn
(Register of Deeds)

By: Deputy

3610301020