

CERTIFIED LAND CORNER RESTORATION

Index No. U - Z

State of Wisconsin

County of Oneida } ss.

History of original corner establishment:
No evidence of any previous corner.


I, Glen Barker, do hereby certify that on the 12th day of June, 1984, I ~~found~~ established the SW 1/16 corner of Section 30, Township 36, North, Range 10 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Description of corner evidence found:
Corner established by subdivision of the SW 1/4.
Corner sets 1336.66' of EC 1/16 and 1253.37' of SC 1/16.

Resident witnesses:

N. Spiess

H. Wagoner



T36N R10E


S1682

T36N R10E

SW 1/16 S 30

Marked NRTs:
Black Spruce 5" S50W 24.93'
Black Spruce 5" S13E 25.05'
scribed 1/16 B.T.

CPI-1984



○ = Corner monument restored.

Description of monument and accessories I established to perpetuate the original location of this corner.

Set a 1" iron pipe with 2" diameter alloy cap, stamped:

Monument projects 18" above ground.

Marked NRTs:

Black Spruce 5" S50W 24.93'

Black Spruce 5" S13E 25.05'

scribed 1/16 B.T.

Dated at Rhinelander, Wis., this 8th day of August, 1984.

Signature Glen Barker Title Registered Land Surveyor Registration No. S1682
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida I hereby certify that the within instrument was filed in this office for record on the 10th day of December, 1984 at 11:30 o'clock A. M.

Donna Verage Tucker
(Register of Deeds)

By _____ Deputy

3610301030