

CERTIFIED LAND CORNER RESTORATION

Index No. Y-19

State of Wisconsin

County of Oneida } ss.



I Phillip T. Hansen do hereby certify that on the 9th day of July, 19 79, I found evidence of the SC 1/16 corner of Section 35 Township 36, North, Range 10 East, Fourth Principal Meridian,

as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

Jim Clafflin

Herb Wagoner



○ = Corner monument restored.

History of original corner establishment:

Corner established by Goddard and crew, Ripco surveyors, in 1960. Ran random line south from previously established C 1/4 corner to S 1/4 corner bearing S 4° 32' E, distance 58.33-3/4 chains. Set SC 1/16 at 29.17 chains intermediate.

Marked NBT's -
Maple 7" S44°E 24 links
Maple 5" S80°W 14-3/4 links

Description of corner evidence found:

Recovered Ripco's 3/4" iron pipe with 2" diameter alloy cap in good condition. Cap stamped: Monument projects 24" above ground.

Recovered Lawrence's 6" squared cedar post, scribed SC 1/16 S35, SC 1/16 S35, which bears S 35° E 15.0 links. Will use Ripco's monument as this was established with transit.

Recovered OBT's -
Maple 7" S44°E (S61°E) 24.0 links (23.7 links) scribed CS 1/16 BT. S35
Maple 5" S80°W (S83°W) 14 links, now dead and down. CS + 1/16
RIPCO

Description of monument and accessories I established to perpetuate the original location of this corner.
Monument left in place as recovered.

Marked NBT's -
Maple 6" S25°W 18.7 links
Maple 5" N17°W 16.2 links
both scribed 1/16 BT.

Dated at Rhineland, Wis., this 10th day of July, 19 79.

Signature Phillip T. Hansen Title Registered Land Surveyor Registration No. S-498
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida. I hereby certify that the within instrument was filed in this office for record on the 7th day of August, 19 79 at 1:00 o'clock P. M.

Veronica Thomas-Randall
(Register of Deeds)

By _____ Deputy

3610351020