

CERTIFIED LAND CORNER RESTORATION

Index No. W-1



3610363000

State of Wisconsin }
County of Oneida } ss.

I, Philip T. Hansen, do hereby certify that on the 12th day of December, 1977, I found evidence of the N 1/16 corner of Section 31 & 36 Township 36, North, Range 10 & 11 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

Glen Barker
Jim Claflin
Herb Wagoner



○ = Corner monument restored.

History of original corner establishment:

Corner established by H.C. Lawrence, Registered Land Surveyor, in 1960. Ran random line S 10° E from Section Corner 25, 30, 31 & 36 a distance of 80.30 chains to close out 2.06 chains east of Township corner. Established 1/4 corner at 103 links west at 40.15 chains intermediate. Established N 1/16 corner at 20.07½ chains, 51½ links west. No trees suitable for BTs.

Description of corner evidence found:

Recovered 4" squared cedar post, standing 4 ft. above ice, in fair condition. Post was scribed N 1/16, S31, R11E, N 1/16 T36N S-36 R10E. Post was in fair condition.

No evidence of any BT's recovered.

Description of monument and accessories I established to perpetuate the original location of this corner.

Replaced wood post with 1½" iron pipe with 2" brass cap, stamped: Monument projects 1" above ice. Corner sets about 4 chains south of the north edge of old beaver flowage. No suitable trees available for BT's. Set Lawrence's post firmly beside the iron pipe.

S498
T36N
R
10 36 + 31 11
E E
CFI-1977

Dated at Rhineland, Wis., this 19th day of December, 1977

Signature: Philip T. Hansen Title: Registered Land Surveyor Registration No. S-498
(County Surveyor, Registered Land Surveyor, or other duly authorized official)
Oneida

Office of Register of Deeds, County of Oneida, I hereby certify that the within instrument was filed in this office for record on the 3rd day of January, 1978 at 3:00 o'clock P M.

Doris Verage Kuehn
(Register of Deeds)

By Joseph M. Boomer Deputy

FORM 985 H. C. MILLER CO., MILWAUKEE