

CERTIFIED LAND CORNER RESTORATION


Index No. **N-23**

State of Wisconsin


County of Oneida } ss.

I Phillip T. Hansen, do hereby certify that on the 4th day of December, 1974, I found evidence of the 1/4 corner of S 13-24 Township 36, North, Range 11 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:



T36N, R11E



○ = Corner monument restored.

CERTIFIED LAND CORNER RESTORATION

History of original corner establishment:

Original corner established by Wm. E. Dougherty, Gov't Deputy Surveyor, 1859.

Resurvey by B.F. Dorr in 1899.

Y. birch 12"	N74E	19 1/2 lks.
Hemlock 8"	N13W	18-3/4 lks.
Aspen 6"	N10E	5 lks.
Aspen 6"	S45W	12 lks.

H.C. Lawrence, Reg. Surveyor states that in 1956 he recovered the point of Dorr's stake, the birch BT was down, but hemlock BT was green and standing. He set a new cedar post and made new bearing trees. Hemlock 9", S70W, 31 1/2 lks. Y. birch 20", N250E, 63 lks.

Description of corner evidence found:
 Recovered H.C. Lawrence's 4" cedar post, squared and scribed S-13 1/4 S-24 1/4 in good condition.

Recovered BT's	Birch stump	N74E	19 1/2 lks.
	Hemlock 8"	N13W	18-3/4 lks.
	Hemlock 9"	S7W	31 1/2 lks.
	Y. birch 20"	N25E	63 lks.

Description of monument and accessories I established to perpetuate the original location of this corner.
Set new 2-1/2" x 5' galvanized iron pipe with brass cap stamped as follows -

No new BT's

S498
T36N, R11E

S 13
1/4
S 14

CPI-1974

Dated at Rhinelander, Wis., this 16th day of June, 1975

Signature Phillip T. Hansen Title Registered Land Surveyor Registration No. S-498
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida
I hereby certify that the within instrument was filed in this office for record on the 1st day of October, 1975
at 3:00 o'clock P. M.

Doris Verne Fischer
(Register of Deeds)

By: _____ Deputy

361130020