

CERTIFIED LAND CORNER RESTORATION

Index No. **V-5**

State of Wisconsin

County of Oneida } ss.

History of original corner establishment: Original corner established by Wm. E. Dougherty, Deputy Surveyor, in 1859, from which Tamarack 10" bears N61°W, 5 links and Cedar 5" bears S65°E, 6 links.

Corner recovered by B.F. Dorr, County Surveyor, in 1886. Recovered original BT's, marked NBT's - Sugar 8" N57°W, 39-3/4 links and Hemlock 10" S7°E, 33 1/2 links. Corner recovered by H.C. Lawrence, Registered Land Surveyor, in 1950. Recovered Dorr's Sugar 8", which was now 18", standing green. Hemlock 10" was down and badly rotted. Marked NBT's - Twin Maple 14" N40°E, 16 links; Ironwood 6" S51°W, 21 links; Basswood stump 24" S80°E, 28-3/4 links. Set 3" hemlock post.

Description of corner evidence found:

Recovered H.C. Lawrence's 3" hemlock post, squared and scribed S29, 30, 31 & 32 in very poor condition. Rock cairn around post.
Recovered Dorr's OBT - Sugar 8" (now 24") N57°W (N60°W) 39-3/4 links. Part of scribe marks visible inside open face.
H.C. Lawrence's twin maple, now down and rotted.
Recovered basswood stump 24" S80°E, 28-3/4 links, now badly rotted.

Description of monument and accessories I established to perpetuate the original location of this corner.

Replaced hemlock post with 2 1/2" Bernitsen A-1 Federal Monument (O.C.C.) Cap stamped: Monument projects 12" above ground.
Replaced rock cairn around base.
Marked NBT's - Sugar 10" N62°E, 39.4 links
Sugar 10" S23°W, 22.1 links
Sugar 7" S30°E, 19.9 links
Sugar 6" N76°W, 20.4 links,
all scribed SC BT.
S498
T36N
30+29
31+32
R11E
1978

Some old barbed wire nailed to trees around corner.

Dated at Rhinelander Wis., this 13th day of January, 1978.

Signature Philip P. Stewart Title Registered Land Surveyor Registration No. S-498
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida
at 1:45 o'clock P. M. on the 30th day of January, 1978.
I hereby certify that the within

By Dorcas Verage Tucker (Register of Deeds)

By SC Deputy

I Phillip T. Hansen do hereby certify that on the 11th day of January, 1978, I found evidence of the Section corner of Secs. 29, 30, 31, 32 Township 36 North, Range 11 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

Glen Barker

Jim Clafflin

Herb Wagoner

