

CERTIFIED LAND CORNER RESTORATION

Index No. A-4

State of Wisconsin

County of Oneida } ss.

I Phillip T. Hansen, do hereby certify that on the 18th day of April, 1979, I ~~found~~ ~~established~~ ~~the~~ found the E 1/16 corner of Sections 31 & 6



Township 36 & 35, North, Range 11 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

Glen Parker

Jim Clafflin

Herb Wassoner



○ = Corner monument restored.

History of original corner establishment:  
No records of any previous survey.

Description of corner evidence found:  
No evidence of any corner recovered.  
Corner established by traverse and computation. Ran traverse from 1/4 corner between sections 31 and 6 west to section corners 31, 32, 5 and 6. Computed distance 2617.47' at bearing N 89° 31' 05" E. Set E 1/16 corner at 1308.735 feet intermediate.

Description of monument and accessories I established to perpetuate the original location of this corner.  
Set 1-1/2" iron pipe with 2" brass cap, projecting 1 1/2" - cap stamped:  
Marked NBT's -  
W. Birch 10" N15°E 39.35', scribed 1/16 BT.  
W. Ash 6" S85°W 76.85', scribed 1/16 BT.

S498  
T36N R11E  
S+31  
S+6  
T35N R11E  
CPI-1979

Dated at Rhineland, Wis., this 30th day of April, 1979.

Signature Phillip T. Hansen Title Registered Land Surveyor Registration No. S-498  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida, I hereby certify that the within instrument was filed in this office for record on the 18th day of April, 1979 at 2:00 o'clock P.M.

Gene L. Briggs  
(Register of Deeds)

By Gene L. Briggs Deputy

3611310010