


CERTIFIED LAND CORNER RESTORATION

Index No. X-16


State of Wisconsin }
County of Oneida } ss.

I Daniel K. Pleoeger, do hereby
certify that on the 18th day
of November, 1981, I ~~restored~~
Est. ~~restored~~ of the EC. 1/16
corner of Section 34
Township 36, North, Range
11 East, Fourth Principal Meridian,
as described hereon; and that from this evidence
I established a new monument and accessories
as described hereon to perpetuate the original
location of this corner.

Resident witnesses:



T36N R11E



○ = Corner monument restored.

History of original corner establishment:
No evidence of any previous corner.

Description of corner evidence found:
Total distance from 1/4 corner between sections 34 & 35 to C 1/4 section 34 is
2814.688 ft. at bearing N81-40-52W. Set EC 1/16 1407.344 ft. intermediate.

Description of monument and accessories I established to perpetuate the original location of this corner.
Set a 1 1/2" iron pipe with 2" diameter aluminum cap stamped:
Monument projects 18" above ground.

Marked NBTs:
Sugar 8" N18E 36.92 ft. EC 1/16 S | 34
Sugar 7" S60E 8.27 ft. T36N R11E
Scribed 1/16 - B.T. CPI - 1981

Dated at Rhinelander, Wis., this 8th day of January, 1982.

Signature Daniel K. Pleoeger Title Registered Land Surveyor Registration No. 1537
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida
Instrument was filed in this office for record on the 27th day of March, 1982
at 10:35 o'clock M.
Donna Lange Truck
(Register of Deeds)

By: Deputy

3611342010