

CERTIFIED LAND CORNER RESTORATION

Index No. **D-24**

State of Wisconsin


County of Oneida } ss.

I Phillip T. Hansen, do hereby certify that on the 20th day of April, 1977, I found evidence of the SE 1/16 corner of Section 1, Township 37, North, Range 8 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

Jim Claffin

Herb Wagoner



T37N R8E


History of original corner establishment:
 Corner established by N. Loftus, Ripco Surveyor, in 1960. Ran random line North from E 1/16 corner south line, bearing 360° mag. 39.94 chains to close out 22 links west of EC 1/16 corner. Set SE 1/16 corner at 19.97 chains, 11 links east. Corrected bearing N 0° 19' E. Ran random line west, bearing 267° 54' mag. from S 1/16, closed out 60 links south at 20.73 at SE 1/16 corner.

Marked NBTs - Red Oak 7" N10°W, 10 links.
 Red Oak 8" S34°W, 26½ links.

Description of corner evidence found:

Recovered 1" iron pipe with 2" brass cap in good condition. Cap stamped:
 Recovered OBTs - Red Oak 7" N10°W, 10.0 links, scribed SE 1/16 BT.
 Red Oak 8" S34°W, 26.5 links (26.0 lks), scribing not legible. T37N R8E
 Monument projects 20" above ground. SE 1/16 S 11
 RIPCO

Description of monument and accessories I established to perpetuate the original location of this corner. As monument was recovered in good condition and firmly in ground, it was left as recovered. No additional accessories were established.



○ = Corner monument restored.

Dated at Rhineland, Wis., this 4th day of May, 1977.

Signature Phillip T. Hansen Title Registered Land Surveyor Registration No. S-498
 (County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida, 6th day of May, 1977.
 I hereby certify that the within instrument was filed in this office for record on the 6th day of May, 1977 at 1:00 o'clock P. M.

Doree Verage Kuehn
 (Register of Deeds)

By _____ Deputy

3708011010