

CERTIFIED LAND CORNER RESTORATION



Index No. **D-22**

State of Wisconsin }
 County of Oneida } ss.

I Phillip T. Hansen, do hereby certify that on the 20th day of April, 1977, I found evidence of the SW 1/16 corner of Section 1 Township 37 North, Range 8 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

Jim Clafflin
Herb Wagoner



○ = Corner monument restored.

History of original corner establishment:

Corner established by N. Loftus, Ripco Surveyor, in 1960. Ran random line East from S 1/16 west line, bearing 88° 30' mag. 41.25 chains to close out 59 links north of SW 1/16 corner. Set SW 1/16 at 20.625 chains 29 1/2 links south. Marked NBTs - Cedar 8" N7°W, 25 1/2 links and Black Spruce 6" S40°E, 29 1/2 links. Ran random line south, bearing 180° 30' mag. from CW 1/16, 19.68 chains to close out 28 1/2 links east of SW 1/16 corner.

Description of corner evidence found:

Recovered 1" iron pipe with 2" square brass cap projecting 20" above ground. Cap stamped: Monument recovered in good condition and firmly in ground.
 Recovered OBTs - Cedar 8" (10") N7°W (N2°W) 25.5 links, scribed SW 1/16 BT.
 Black Spruce 6" S40°E, 29.5 links, partially dead.

T37N R8E
 SW 1/16 **S 1**
 RIPCO

Description of monument and accessories I established to perpetuate the original location of this corner. As monument was recovered in good condition, it was left as recovered.

Marked NBT - Black Spruce 8" S72°E, 65.0 links, scribed 1/16 BT.

Dated at Rhinelander, Wis., this 4th day of May, 1977.

Signature: Phillip T. Hansen Title: Registered Land Surveyor Registration No. S-498
 (County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida. I hereby certify that the within instrument was filed in this office for record on the 6th day of May, 1977 at 1:00 o'clock P. M.

Dorice LePage Kuehn
 (Register of Deeds)

By: _____ Deputy

02-10108073