

CERTIFIED LAND CORNER RESTORATION

Index No. **B-22**

State of Wisconsin

County of Oneida } ss.

I Phillip T. Hansen do hereby certify that on the 1st day of April, 1977, I found



evidence of the NW 1/16 corner of Section 1 Township 37, North, Range 8 East, Fourth Principal Meridian,

as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

Jim Claflin

Herb Wagoner



○ = Corner monument restored.

History of original corner establishment:

Corner established by N. Loftus, Ripco Surveyor, in 1960. From re-established W 1/16 corner on north line, ran 180° 03' mag., 37.37 chains to close out 92 links east of W.C. 1/16 corner. Ran random line 268° 06' mag. from NW 1/16, 40.36 chains to close out 30½ links north of N 1/16 corner on west line. Set NW 1/16 corner at 20.18 chains 15½ links south.

Marked BTs - Black Spruce 4" N2°E, 19½ links and Red Pine 6" S76°E, 34½ links. Corrected bearing S 87° 40' W.

Description of corner evidence found:

Recovered 1" iron pipe with 2" square brass cap in good condition and firmly in ground. Cap stamped:

Monument projects 20" above ground.

Recovered BT's - Black Spruce 4" N2°E, 19.5 links, now dead.

Red Pine 6" (8") S76°E, 34.5 links, scribing not legible. NW 1/16 S 1

T37N R8E
RIPCO

Description of monument and accessories I established to perpetuate the original location of this corner.

As the monument was recovered in good condition and firmly set in ground, it was left as recovered.

NBT - Black Spruce 6" N53°E, 51.7 links, scribed 1/16 BT.

Dated at Rhinelander, Wis., this 3rd day of May, 1977.

Signature Phillip T. Hansen Title Registered Land Surveyor Registration No. S-498
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida at 9:00 o'clock M. day of May, 1977. I hereby certify that the within instrument was filed in this office for record on the 5th day of May, 1977.

Doree Verage Fisher
(Register of Deeds)

By _____ Deputy

3708013030