

CERTIFIED LAND CORNER RESTORATION

Index No. G-25

State of Wisconsin



County of Oneida } ss.

I Phillip T. Hansen, do hereby certify that on the 20th day of April, 1977, I found evidence of the Quarter corner of Section 12 & 7 Township 37, North, Range 8 & 9 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

Jim Clarlin

Herb Wagoner



○ = Corner monument restored.

History of original corner establishment:

Original Corner established by H.C. Fellows, Deputy Surveyor, in 1860, from which Red Oak 8" bears S32°E, 8 links and Red Oak 9" bears N 87° W, 14 links. Corner re-established by Ripco surveyors in 1960. Ran a random line N0°30'E from SE corner section 12 and at 81.24 closed out 4.23 chains east of Section Corner. Set 1/4 corner at 40.62 chains, 2.15 chains west. Marked NBTs - Maple 4" N13°E, 30.1 links. Oak 4" S20°E, 47 links.

Description of corner evidence found:

Recovered 1-3/4" iron pipe with 3" square brass cap in excellent condition and set firmly in ground.

Monument projects 24" above ground. Cap stamped:

Recovered OBts - Maple 4" (5") N13°E (N18°E) 30.5 links, scribed 1/4 BT.
Oak 4" (5") S20°E (S16°E) 47.0 links.

T37N R8E T37N R9E
S12 | S7
1/4

Description of monument and accessories I established to perpetuate the original location of this corner.

As monument was recovered in excellent condition, it was left as found.

NBTs - Maple 7" N72°W, 11.5 links, scribed 1/4 BT.
Oak 7" N22°W, 19.5 links, scribed 1/4 BT.

Dated at Rhineland, Wis., this 3rd day of May, 1977

Signature: Phillip T. Hansen Title Registered Land Surveyor Registration No. S-498
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Registrar of Deeds, County of Oneida, I hereby certify that the within instrument was filed in this office for record on the 5th day of May, 1977 at 2:00 o'clock P. M.

Debra Neugebauer
(Registrar of Deeds)

By: _____ Deputy

00002218073