

6	5	4	3	2	1
7	8	9	10	11	12
13	14	15	16	17	18
19	20	21	22	23	24
25	26	27	28	29	30
31	32	33	34	35	36

RECEIVED & FILED  
 Price County Surveyor's Office  
 Date 2009.07.23  
 By [Signature]  
 PCS File No. N3822  
E0300

**CERTIFIED LAND CORNER RESTORATION**  
 REGISTERED OFFICE OF ONEIDA COUNTY  
 FILED

T 39 N. R 03 E

MAR - 9 2016

STATE OF WISCONSIN }  
 COUNTY OF Price } ss.

I, Randy R. Erickson, do hereby certify that on the 15 day of Sept., 2008,  
 AT            O'CLOCK            M  
KYLE J. FRANSON  
 REGISTERED LAND SURVEYOR


I found evidence of the East Quarter corner of Section 24,  
 Township 39 North, Range 03 East, Fourth Principal Meridian, as described  
 hereon; and that from this evidence I established a new monument and accessories as described  
 hereon to perpetuate the original location of this corner.

**Description of Original monument and accessories and subsequent restorations:**

1864 Alex Anderson set a wood post and marked Bearing Trees:  
 Hemlock 9" N 32° W 22 links Hemlock 6" N 50° E 10 links  
 1936 U.S. General Land Office dependent resurvey recovered remains of  
 original Bearing trees, Set an iron post, 3 feet long, 27" in ground, 1"  
 diameter, with a brass cap stamped to identify the corner. Original BTs:  
 Hemlock 7" N 69 3/4° E 10 links Hemlock stub 12" N 39° W 22 links  
 Marked new Bearing Trees:  
 Cedar 5" N 13 1/2° E 78 links Cedar 5" N 60 1/2° W 17 links

**Description of corner evidence found:**

Found 1936 iron post in place. Found both 1936 cedar Bearing Trees in place  
 and well



**Description of monument and accessories I established to perpetuate the location of this corner:**

Left 1936 iron post monument in place. Measured to Bearing Trees  
 Cedar 17" N 13 E 51.5 feet (GLO 1936)  
 Cedar 9" N 60° W 11.2 feet (GLO 1936)  
 Cedar 10" S 61° W 35.67 feet (new)  
 steel Sign Post North 0.9 feet

Established Wisconsin North Zone State Plane Coordinates for Corner:

N 250528.174 E 1957417.941 NAD 83 1991 u.s. foot

Section	24		
Town	39	North	
Range	03	East	

● - Corner monument restored

Resident witness \_\_\_\_\_  
 Dated at Park Falls Wisconsin, this 29 day of Sept.  
20 08.  
 Signature [Signature] Title Reg. Land Surveyor  
 Surveyors Registration No. 1897.  
 Office of \_\_\_\_\_ County of \_\_\_\_\_  
 I hereby certify that the within instrument was filed in this office for record  
 on the \_\_\_\_\_ day of \_\_\_\_\_ 20\_\_\_\_, and was filed in Book  
 No. \_\_\_\_\_ Page No. \_\_\_\_\_ of County Records.  
 Signature \_\_\_\_\_ Title \_\_\_\_\_

Township 39 North, Range 03 East, Section 24, Index No. \_\_\_\_\_, Page No. \_\_\_\_\_

N3822 E0300 2008 P-1