



① N $\frac{1}{4}$  NE $\frac{1}{4}$

RECEIVED & FILED	1697
Oneida County Surveyor's Office	
Date FEB. 5 1988	
By P.M.	
OCS Area #	

② Mardon Cor - North line - East of Shallow Lhs OBT. PW 8" - N62°E - 16 0 ft post (Vaughn 6/22/10)

③ N $\frac{1}{4}$  Sec 22 Found over run of 1.47 between ~~1.15~~ both orig. M.C. & set 1 $\frac{1}{4}$  Cor. at 1.15 east of W.M.C. & about 75 lfs west of present lake shore. from 4" - S88°W - 23' fence 5" - S15°E - 30'. (Vaughn 6/22/10) south from N $\frac{1}{4}$  Cor. 2.38 to lake; 940 over lake (Vaughn 6/22/10)

L697

L697

④ Meander Cor - North Line - West of Shallow Lake at 39.255 east  
of NW Cor. fell 127 north of MC.. found Sec OBT. OK, set post. (Vaughn 6/22/10)

⑤ N<sup>1/4</sup> NW<sup>1/4</sup> set 1/8 post at 19.10 - No trees near. (Vaughn 6/22/10)

⑥ Meander Cor - North Line - East of Stone

⑦ NW Cor. Sec. 22 at 39.54 east of N<sup>1/4</sup> sec 27 found NW O.B.T. to be 147  
instead of 167 a low step. (Don 9/26/94) NW Cor. O.K. (Vaughn 6/22/10) 143. of NW  
O.B.T. measures 147 as Don says. Set new post. PN 10° - N 34° W - 1.135 ch. (Holl  
6/3/33)

⑫ Wander Cr - West Line - South of Tom Doyle Didn't find orig MC  
M.C. in line with orig MC on north shore of lake & SW Cr., 14.60 north of SW  
Cr. Bush 8"-N9°E-66. (Vaughn 12/4/02)

⑬ W 1/4 SW 1/4 Was a shortage of 7.70 between SW Cr & M.C. rods of Tom Doyle  
proportioned 1/8 Cr so it falls at 13.06 north of SW Cr. Doyle 9"-N25°E-34;  
Bush 10"-S4°W-22 (Vaughn 12/4/02)

⑭ SW Cr. sec 22 Found NE obt. down, marks OK. NW obt.  
marks nearly gone. Two other marked trees not called for in orig. notes. Set  
post. (Vaughn 12/4/02) Located SW Cr. at east edge of large fence post in north line  
lane, 20.06 west of E of N/S road (Vaughn says 20.22 from 1/8 line) Mr. Jungzen  
claims he set this fence post alongside of old corner post. (Hall 6/3/33)

⑮ S 1/4 SW 1/4 Set 1/8 corner at 20.015 Cedar 12"-555°W-32 (Vaughn  
6/22/10)

Sec 22-38-8.697m

1.697m

⑧ Meander Cr - West line - South of Tom Doyl at 35.70 north of orig MC  
on north shore of Tom Doyl Lake fell 34 $\frac{1}{2}$  west of orig MC south side of lake.  
Found post & both O.B.T. (Vaughn 6/2/10) Found post hole & both O.B.T. Set new  
post. PN 13" - S 74 $^{\circ}$  W - 0.827 ch; Osh 6" - N 51 $^{\circ}$  E - 0.172 ch. Corner is 65 $^{\circ}$  back  
south of shore. (Hall 6/3/33)

⑨ W $\frac{1}{4}$  · NW $\frac{1}{4}$

⑩ W $\frac{1}{4}$  Sec 22 No sign of agl corner... set  $\frac{1}{4}$  at 8.485 north of orig MC  
on north shore of Tom. Doyl Lake. - No trees near - piled rocks around post  
(Vaughn 6/22/10) at 8.42 north found fence & corner post; at 8.481 set pitch post  
flush with posthole. Center of large rock bears S 12 $^{\circ}$  E - 22; N/S fence bears  
east 1.2 feet; E/W fence bears south 3.9 feet (Hall 6/3/33) True  $\frac{1}{4}$  corner  
would be 1.083 ch north of here. (Hall 6/3/33)

⑪ Meander Cr - West line - North of Tom Doyl at 30.02 north of SW  
Cr. fell 0.101 east of MC. (Vaughn 12/4/02) Drove 1 $\frac{1}{2}$ " iron pipe in lake from  
both O.B.T. New B.T. PN 20" - N 85 $^{\circ}$  E - 0.707 ch. Set Witness corner 20 ch  
north on land, a conc. monument with cross caps. (Hall 6/3/33)

1.697m

1.697m

(20) Ctr. Sec 22 lot ctr. PW (sp.) 18" - N 21° W - 26  
PW (sp.) 20" - S 36° E - 1.30. (Vaughn 6/22/10) L 697M

39.67	41.09
38.28	41.23

(21) N 1/4 SE 1/4 PW 20" - N 70° E - 23; PW 1" - S 88° E - 0.465 ch (Vaughn 6/22/10)

(22) Meander Cor - 1 1/2 1/4 Lino - North of Twin Lake at 59.00 south of  
N 1/4 Cor of 1291 south of ctr. PW 14" - N 88° W - 32; Thm. 9" - N 76° E - 0.415 ch.  
(Vaughn 6/22/10) Drove river bank next to Vaughns post. His Thm is 0.145 meters  
of 0.515. New Th. PW 14" - N 27° E - 0.482 ch; PW 20" - N 80° W - 0.660. (Hull  
6/3/33)

(23) Ctr. SW 1/4 lot 1/4 cor. Bush 12" - N 54° W - 0.385. (Vaughn 6/22/10)

L 697M

1 1/2 1/4

L 697M

Sec 22 - 38-8

⑯ Meander Cor - South line - West of Twin Lake at 35.35 east & SW 1/4  
ell 54 1/2 north of orig. MC. Found old post & stp. of O.B.T. Pw 12" - N28°W - 93. Set new  
post. (Vaughn 6/22/10) at 35.386 east

⑰ DS 1/4 Sec 22 lot 1/4 Cor. at 46.9 east of W.M.C. (Vaughn 6/22/10)

⑱ Meander Cor - South line - East of Twin Lake Found corners  
between East of West MC to be 14.71 (Vaughn 6/22/10)

⑲ S 1/4 / SE 1/4 Is shown in Gage Co., 1930 Map

See 22-38-8  
L6974

L6974

24 Meander cor - S $\frac{1}{8}$  Lins - West of Twin Lake Tom. 3" - East - 0.010 ch.  
Tom 3" - S $10^{\circ}$  W - 0.040 ch. (Vaughn 6/22/10)

25 Meander cor - S $\frac{1}{8}$  Lins - East of Tom Doyle lot 6x6 conc. mon.  
for MC. on south lins of Govt. Lot 3, 12' east of shore. PW 13" - N - 0.212 ch.  
PW 20" - S - 0.144; a 1" iron pipe is N $88^{\circ}$  W - 0.152 ch. (Held 6/29/33)

26 Meander cor - South lins - West of Kate Pier lots Aug. M.C. (Nelson 1954)  
Gentz 1978 map has wood post here  
Also is MC south of Kate Pier later (betw 27/26)

L6974

L6974