

PROJECT	SHEET NO.	TOTAL SHEETS
50706(3)	2B	45

## DETAIL SUMMARY OF MISCELLANEOUS QUANTITIES

### GRANULAR SUBBASE COURSE:

Station - Station	C.Y./STA.	CU.YDS.
160+00 - 169+00	0	0
169+00 - 181+00	122	1,464
181+00 - 239+00	0	0
239+00 - 290+00	122	6,222
290+00 - 362+00	0	0
6 Private Entrances		134
2 Town Roads		80
<b>TOTAL</b>		<b>7,900</b>

### HEAVY

### RIPRAP ON SLOPES:

Station - Station	Side	CU.YDS.
237+50 - 241+00	Lt.	305
237+50 - 241+00	Rt.	305
<b>TOTAL</b>		<b>610</b>

### OBLITERATING OLD ROAD:

Station - Station	Side	STATIONS
160+50 - 164+00	Rt.	3.5
189+00 - 193+00	Lt.	4.0
355+00 - 356+00	Lt.	1.0
<b>TOTAL</b>		<b>8.5</b>

### STEEL PLATE BEAM GUARD:

Station - Station	Side	LENGTH
237+30.0 - 238+72.0	Lt.	141.5
237+30.0 - 238+72.0	Rt.	141.5
239+28.0 - 240+69.5	Lt.	141.5
239+28.0 - 240+69.5	Rt.	141.5
<b>TOTAL</b>		<b>566.0</b>