

CERTIFIED LAND CORNER RESTORATION

Index No. H-6



State of Wisconsin

County of Oneida } ss.

I Philip T. Hansen, do hereby certify that on the 19th day of May, 1975, I found evidence of the SW-1/16 corner of Section 8 Township 35 North, Range 11 E, Fourth Principal Meridian,

as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:



○ = Corner monument restored.

CERTIFIED LAND CORNER RESTORATION

History of original corner establishment:

Corner established by H.C. Lawrence, Registered Land Surveyor, during his retracement survey in 1954. From his established SC-1/16 corner he ran S87°0'W, 41.44 chains to intersect the line between Section 7 and 8, 35 links south of D.H. Vaughan's S-1/16 corner. Set SW-1/16 corner 4" hemlock post equidistant, 17 links north of random line, from which white birch 14" bears N20°W, 40 links and basswood 8" bears S15°W, 32 links. Corrected bearing of line S87°30'W.

Description of corner evidence found:

Recovered 4" hemlock post, squared and scribed, SW-1/16 S8, SW-1/16 S8 in good condition.
 Recovered OBT's: White birch 14" N17°W 41.2 links scribed SW-1/16BT
 Basswood 10" S16°W 32.4 links scribed SW-1/16BT

Description of monument and accessories I established to perpetuate the original location of this corner.

Replaced 4" hemlock post with 1-1/2 OD iron pipe w/2" brass cap stamped - S498
 Unable to get I.P. more than 20" below surface because of bedrock or large stone. A rock cartton was built up around the pipe. T35N R11E

SW-1/16 S 8
 CPI-1975

Dated at Rhineland, Wis., this 6th day of June, 1975.

Signature Philip T. Hansen Title Registered Land Surveyor Registration No. S-498
 (County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida. I hereby certify that the within instrument was filed in this office for record on the 1st day of October, 1975 at 3:00 o'clock P. M.

Donna Heritage Kuebler
 (Register of Deeds)

By: _____ Deputy

3511081080