

CERTIFIED LAND CORNER RESTORATION


Index No. **K-23**

State of Wisconsin

County of Oneida } ss.

I Phillip T. Hansen, do hereby certify that on the 7th day of June, 1977, I found evidence of the NC 1/16 corner of Sec. 13 Township 35, North, Range 11 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.


Resident witnesses:  
Glen Barker  
Jim Ciaflin  
Herb Wagoner



History of original corner establishment:  
Corner established by H.C. Lawrence, Registered Land Surveyor, in 1958. Ran E-W and N-S 1/4 lines from restored 1/4 corners to establish the C 1/4. Set NC 1/16 at 19.98 chains intermediate.  
Marked NBTs - White Pine stump 20" N77°E, 119 1/2 links  
Black Cherry 9" S19°W, 97 links

Description of corner evidence found:  
Recovered 5" squared cedar post, scribed NC 1/16 S13, NC 1/16 S13, in fair condition. Post sets in the corner of fence line south and west.  
Recovered White Pine stump 20" N77°E, 119 1/2 links, now badly decomposed.  
Black Cherry 9" (18") S19°W, 97 links, scribed S13 BT.

Description of monument and accessories I established to perpetuate the original location of this corner.  
Replaced cedar post with 1 1/2" iron pipe with brass cap, stamped: S498  
Monument projects 2" above ground. T35N R11E  
Marked NBTs - Black Cherry 6" N43°W, 122.7 links, scribed 1/16 BT. NC 1/16 S 13  
No other trees suitable. CPI-1977  
Placed rock cairn around base of monument.



○ = Corner monument restored.

Dated at Rhineland, Wis., this 9th day of June, 1977

Signature Phillip T. Hansen Title Registered Land Surveyor Registration No. S-498  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida  
Instrument was filed in this office for record on the 3rd day of June, 1977 at 9:20 o'clock A. M. I hereby certify that the within

Terrie Urzayg Tuelke  
(Register of Deeds)

By Joseph M. Baorn Deputy

351133020