

CERTIFIED LAND CORNER RESTORATION



Index No. 7-8

State of Wisconsin } ss.
County of Oneida

I, Phillip T. Hansen, do hereby certify that on the 10th day of August, 1978, I established the EC 1/16 corner of Section 29, Township 35 North, Range 11 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

- Glen Barker
- Jim Clafin
- Herb Wagener
- John Masbaum



History of original corner establishment:
No records of any previous survey.

Description of corner evidence found:

No evidence of any corner recovered.
Corner established by traverse and computation. Computed distance from E 1/4 corner to established C 1/4 is 2641.185 feet at bearing N 89° 49' 26" W.
Set EC 1/16 at 1320.593 feet intermediate.

Description of monument and accessories I established to perpetuate the original location of this corner.
Set 1 1/2" iron pipe with 2" brass cap, projecting 24", stamped:

- Marked NBT's -
- white birch 8" S36°E 36.10' scribed 1/16 BT S498
- white birch 8" N40°W 50.25' scribed 1/16 BT T35N R11E

CPI-1978

Dated at Rhinelander, Wis., this 14th day of August, 1978.

Signature: *Phillip T. Hansen* Title: Registered Land Surveyor Registration No. S-498
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida
Instrument was filed in this office for record on the 21st day of August, 1978, at 1:00 o'clock P.M.

Doris Leage Kuehn
(Register of Deeds)

By: Deputy

3511292010