

CERTIFIED LAND CORNER RESTORATION



P-14 Index No. P-14

State of Wisconsin }
 County of Oneida } ss.

I Philip T. Hansen do hereby
 certify that on the 13th day
 of April 1976, I found
 evidence of the W.C. 1/16
 corner of Sec. 22
 Township 36 North, Range
 9 East, Fourth Principal Meridian,

as described hereon; and that from this evidence
 I established a new monument and accessories
 as described hereon to perpetuate the original
 location of this corner.

Resident witnesses:
 Glen Barker
 Jim Claflin
 Herb Wagoner



○ = Corner monument restored.

History of original corner establishment: Original Corner established by B.F. Dorr, County Surveyor, Ripco Surveyors, Goddard and crew, re-established Corner in 1961.
 From recovered C 1/4 set by Dorr, ran 264° 30' 41.085 chains and closed out 47 lks South of W 1/4 Corner. Corrected bearing S 85° 09' W.
 Set WC 1/16 at 20.5425 chains 23½ lks North. Marked NBTFs - W.Pine 24" S 38° E 34 lks, W.Pine 14" S 5° W 67 lks.
 Set a reference pipe 28 lks South.

Description of corner evidence found: Recovered a RR spike in the South edge of River Bend Road.
 Recovered a 1" iron pipe with aluminum cap 28 lks, South, cap stamped.
 Witness Corner projects 12" above ground.
 Recovered OBT - W.Pine 24" S 38° E 34 lks, scribed CW 1/16 BT.
 W.Pine 14" (16") S 5° W 67 lks, scribed CW 1/16 BT.

C S22 C
 Cor. 28 lks
 North

Description of monument and accessories I established to perpetuate the original location of this corner.
 As the Witness Corner was in very good condition, we left it in place.
 Stamped T36N R9E on the cap.
 No additional accessories established.
 Witness Monument and BTs painted blue.

Dated at Rhinelander, Wis., this 19th day of July, 1976
 Signature *Philip T. Hansen* Title Registered Land Surveyor Registration No. S-498
 (County Surveyor, Registered Land Surveyor, or other duly authorized official)
 Office of Register of Deeds, County of Oneida
 Instrument was filed in this office for record on the 3rd day of August, 1976
 at 10:30 o'clock M.

Dorcas Verge Kuehn
 (Register of Deeds)

By _____ Deputy

3609222030
 3609222032