

CERTIFIED LAND CORNER RESTORATION

Index No. R-2



State of Wisconsin

County of Oneida } ss.

History of original corner establishment:  
No records of any previous survey.

I, Phillip T. Hansen, do hereby certify that on the 16th day of August, 1979, I ~~found~~ ~~relocated~~ ~~of the~~ relocated the W 1/16 corner of Section 19, and 30 Township 36, North, Range 10 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:  
Glen Barker  
Jim Clafin  
Herb Wagoner



○ = Corner monument restored.

3610190030

Description of corner evidence found:  
No evidence of any corner recovered.  
Corner established by traverse and computation. Computed distance from S 1/4 corner to section corner 19, 30, 25, 24, 2762.851 ft. W 1/16 corner set by proportional measurement N 70° 30' 49" E, 1418.325 feet from section corner and 1343.926' from 1/4 corner.

Description of monument and accessories I established to perpetuate the original location of this corner.  
Set a 1-1/2" iron pipe with 2" brass cap, projecting 18", stamped:  
Marked NBT's -  
White Fine 7" S80°W 26.90'  
Red Fine 8" N38°E 21.75'  
both scribed 1/16 BT.  
S498  
T36N R10E  
S 19  
1/4 S+30  
CPI-1979

Dated at Rhineland, Wis. this 20th day of August, 1979.

Signature Phillip T. Hansen Title Registered Land Surveyor Registration No. S-498  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)  
Office of Register of Deeds, County of Oneida, 2/1/1 day of August, 1979  
at 7:00 o'clock P. M. I hereby certify that the within instrument was filed in this office for record on the 2/1/1 day of August, 1979

Doris George Kuhl  
(Register of Deeds)

By: \_\_\_\_\_ Deputy