

CERTIFIED LAND CORNER RESTORATION

Index No. W-19

State of Wisconsin



County of Oneida } ss.

I, Phillip T. Hansen, do hereby certify that on the 9th day of July, 1979, I found evidence of the NC 1/16 corner of Section 35 Township 36, North, Range 10 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

Jim Claflin

Herb Wagoner



○ = Corner monument restored.

History of original corner establishment:

Corner established by Goddard and crew, Ripco surveyors, in 1960. Ran E-W and N-S 1/4 lines to establish the C 1/4. C 1/4 corner sets 58.33-3/4 chains N 4° 32' W of S 1/4 corner, and 41.08 chains S 4° 32' E of N 1/4 corner. Set NC 1/16 at 20.54 chains equidistant. Set monument and marked NBT's -
 White Pine 16" S73°W 33 links
 White Spruce 7" N9°W 41 links

Description of corner evidence found:

Recovered Ripco's 3/4" iron pipe with 2" alloy cap in good condition.
 Recovered H.C. Lawrence's 6" squared cedar post, scribed NC 1/16 S 35, S 53° E, 19.8 links from Ripco's monument. Will accept Ripco's corner as that had been set with transit.
 Recovered OBT's - W. Spruce 7" (10") N9°W 33 links, scribed NC 1/16.
 W. Pine 16" (18") S73°W 33.06 links (our distance 23.0 links)
 scribed CN 1/16 BT.

Description of monument and accessories I established to perpetuate the original location of this corner.
 Monument left in place as recovered.

Cap stamped:
 Marked NBT -
 Black Spruce 8" S44°E 8.8 links, scribed 1/16 BT.
 CN 1/16
 S 35
 RIPCO

Dated at Rhineland, Wis., this 10th day of July, 1979.

Signature Phillip T. Hansen, Title Registered Land Surveyor Registration No. S-498
County Surveyor, Registered Land Surveyor, or other duly authorized official

Office of Register of Deeds, County of Oneida I hereby certify that the within instrument was filed in this office for record on the 7th day of August, 1979 at 10 o'clock M.

Doris Winge Kuehn
(Register of Deeds)

By _____ Deputy

3610353026