

CERTIFIED LAND CORNER RESTORATION



Index No. **E-7**

State of Wisconsin

County of Oneida } ss.

I, Philip T. Hansen, do hereby certify that on the 20th day of March, 1975, I found evidence of the corner of Township North, Range Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:



○ = Corner monument restored.

CERTIFIED LAND CORNER RESTORATION

History of original corner establishment:

Original corner established by Wm. E. Dougherty, Gov. Deputy Surveyor in 1859.
 Ash 6" N44°E 23 links
 Sugar 8" S84°W 31 links
 Corner recovered by D.H. Vaughan, County Surveyor, in 1904. He was unable to find the corner recovered by H.C. Lawrence, Reg. Land Surveyor, in 1946. He set a new 6" cedar post in place of the recovered point from which NBT's black ash, 16" bears S30°E, 33 links, and maple 16" bears N45°W, 40 links.

Description of corner evidence found:

Recovered 6" cedar post, squared, and scribed 1/4 S S5; 1/4 S S8 in fair condition. Post was leaning over and barely in the ground. Because of rocky terrain, post was probably not put in the ground very far.
 Recovered 16" black ash, now a 5' stump, had been cut above the scribing 1/4 S8 NBT.
 Recovered red maple 16", now dying, scribe marks grown over.

Description of monument and accessories I established to perpetuate the original location of this corner.

Replaced old stake with 2 1/2" x 50" galvanized iron pipe w/brass cap, stamped -

NBT's - red maple	7"	S24°W	54 links	scribed	1/4 BT	S498
elm	9"	N50 E	55 links	scribed	1/4 BT	T36N R11E

1/4-C	S	5
	S	8

CPI-1975

Dated at Rhinelander, Wis., this 10th day of June, 1975.

Signature *Philip T. Hansen* Title Registered Land Surveyor Registration No. S-498
 (County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida On site 1st day of October, 1975
 at 3:00 o'clock M. I hereby certify that the within

Tennis George Fuchler
 (Register of Deeds)

By Deputy

3611050020