


CERTIFIED LAND CORNER RESTORATION

Index No. 5-16

State of Wisconsin } ss.  
County of Oneida


I Philip T. Hansen do hereby certify that on the 24th day of January, 19 75, I found evidence of the E-1/16 corner of Section 10 and 15 Township 36 North, Range 11 E, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:



T36N R11E S10

21.77 21.66  
E-1/16



○ = Corner monument restored.

History of original corner establishment:

Corner established by H.C. Lawrence, Registered Land Surveyor, during his retracement survey and subdivision survey dated 1952. He ran a random line N89°00'E from corner of Sec. 9-10-15-16, 86.65 chains to original GLO corner of Sections 10-11-14-15 which was 94 links south.

Set E-1/16 corner, 4" tamarack post at 64.99 chains east and 70-1/2 links south of random line from which maple 10" bears S43°E 35 links and white pine stub 40" bears N25 E 107 links.

Description of corner evidence found:

Recovered 4" cedar post, squared and scribed E-1/16 S10; E-1/16 S15 in poor condition. Recovered maple 10" partly dead but okay, S43°E 35 links scribed S15 BT.

Description of monument and accessories I established to perpetuate the original location of this corner.

Replaced wooden stake with 2-1/2" x 5' galvanized iron pipe w/brass cap stamped -

NBT - Red maple 9" S71°W 79.4 links scribed 1/16 BT

S498  
T36N R11E  
E-1/16 S10  
S15

CPI-1975

Dated at Rhineland, Wis., this 22 day of May, 19 75.

Signature: Philip T. Hansen Title: Registered Land Surveyor Registration No. S-498  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida, I hereby certify that the within instrument was filed in this office for record on the 1st day of October, 19 75 at 3:00 o'clock P. M.

Donna Verage Tucker  
(Register of Deeds)

By: \_\_\_\_\_ Deputy

36 11 10 0010