


CERTIFIED LAND CORNER RESTORATION

Index No. L-23


State of Wisconsin }  
 County of Oneida } ss.

I Phillip T. Hansen, do hereby  
 certify that on the 4th day  
 of December, 1974, I found  
 evidence of the G-1/4  
 corner of 13  
Township 36, North, Range  
11 East, Fourth Principal Meridian,  
 as described hereon; and that from this evidence  
 I established a new monument and accessories  
 as described hereon to perpetuate the original  
 location of this corner.

Resident witnesses.



T36N, R11E



○ = Corner monument restored.

History of original corner establishment:

Original corner established by B.F. Dorr, County Surveyor, in 1897. Retracement survey by H.C. Lawrence, CPI Surveyor, 1950. He states he started from B.F. Dorr's N-1/4 Corner and ran South 0°30'E on random line 77.37 to intersect South line 1.38 chains East of Dorr's 1/4 corner. He ran the East-west 1/4 line at S89°50'E from the West 1/4 corner 84.18 chains to a point 2.16 chains North of East 1/4 corner. Corrected line to intersect C-1/4 Corner with corrected N-S line. Set new cedar post for corner. His results showed that B.F. Dorr did not run the E-W 1/4 line East of the C-1/4 established by him so he disregarded Dorr's C-1/4 Corner.

Description of corner evidence found:

Recovered H.C. Lawrence's post, 4" cedar, squared and scribed S13 C-1/4, S13 C-1/4 standing and in good condition. A 6" squared cedar tree overhanging the corner. Recovered old bearing tree, cedar 10", S46W, 6 lks., scribed C-1/4 BT.

Description of monument and accessories I established to perpetuate the original location of this corner.

Set a 2-1/2" x 5' galvanized iron pipe with brass cap stamped as follows -  
 No new bearing trees.

S498  
 T36N, R11E  
 S13-C-1/4  
 CPI-1974

Dated at Rhineland, Wis., this 16th day of June, 1975.

Signature Phillip T. Hansen, Title Registered Land Surveyor, Registration No. S-498  
 (County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida, lot day of October, 1975  
 at 3:00 o'clock P. M. I hereby certify that the within

Terrie Terence Fisher  
 (Register of Deeds)

By \_\_\_\_\_ Deputy