


CERTIFIED LAND CORNER RESTORATION

Index No. L-20


State of Wisconsin } ss.  
County of Oneida

I Philip T. Hansen, do hereby  
certify that on the 7th day  
of January, 19 75, I found  
evidence of the EC-1/16  
corner of Section 14  
Township 36, North, Range  
11 East, Fourth Principal Meridian,  
as described hereon; and that from this evidence  
I established a new monument and accessories  
as described hereon to perpetuate the original  
location of this corner.

Resident witnesses:



T36N, R11E



○ = Corner monument restored.

History of original corner establishment:

Corner established by H.C. Lawrence during his retracement survey of 1955. Set EC-1/16 corner equidistant between C-1/4 and E-1/4 at 22.01 chains. No record of corner established by other surveyors. No record of bearing trees.

Description of corner evidence found:

Recovered 4" cedar post, squared and scribed S14 EC-1/16 in fair condition. No trace of BT's. Area has been clear-cut and scarified.

Description of monument and accessories I established to perpetuate the original location of this corner.

Set 1" x 5' galvanized iron pipe with 2" brass cap stamped -  
S498  
T36N, R11E  
No trees available for BT's.

EC-1/16 | S14  
CPI-1975

Dated at Rhineland, Wis., this 16th day of June, 19 75.

Signature Philip T. Hansen Title Registered Land Surveyor Registration No. S-498  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida. I hereby certify that the within  
instrument was filed in this office for record on the 1st day of October, 19 75  
at 3:00 o'clock P. M.

John George Yuchak  
Register of Deeds

By: \_\_\_\_\_ Deputy

3611142010