RECEIVED & FILED # 6437
Oneida County Surveyor's Office
Date FEB. 6 1986.
By MJH
OCS Area #

Part of the
SE 1/4 of the SE 1/4
SECTION 7, T38N, R8E
and all of the
N 1/2 of the NE 1/4
SECTION 18, T38N, R8E

Newbold Township
Oneida County, Wisconsin

Scale 1"=100'
0 25' 50' 100' 200'

JOHN H. FISHER & ASSOCIATES, INC.
MINOCQUA, WISCONSIN

I, JAMES M MARQUARDT, Registered Land Surveyor, S-1405, hereby certify that we have surveyed the property shown hereon, that this map is a true and accurate representation thereof, that said survey was performed by order of David Walters, and that we have complied with the applicable requirements of s A-E 5.01 of the Wisconsin Administrative Code

James M. Marquardt
JAMES M MARQUARDT S-1405

Dated Nov. 16, 1978
Revised this 27th day of September, 1979

6437

-1- 6.23 Acres
-2- 7.74 Acres
-3- 5.58 Acres
-4- 6.90 Acres
-5- 17.56 Acres
-6- 5.12 Acres
-7- 6.18 Acres
-8- 7.48 Acres
-9- 7.90 Acres
-5- 2.15 Acres
-5- 1.74 Acres

PRIVATE (OUTLOT 1) ROAD
RIVER ROAD
BLACK LAKE ROAD
EASEMENT
DRIVE
SHORE
NORTH

S 88° 43' 06" E 2485.20' (1/4 Corner to Section Corner)
1/8 CORNER 2"x30" iron pipe set and tamarack post 6" Spruce S82°E, 29.4' 6" Tamarack N82°E, 14.5'
1/16 CORNER 2"x30" iron pipe set and tamarack post 7" Spruce S10°W, 22.7' 6" Spruce N56°W, 13.2'
1/16 CORNER 2"x30" iron pipe set and service post 11" J Pine S43°E, 24.5' 5" Oak N50°E, 16.1'
1/8 CORNER 2"x30" iron pipe set 20" W Pine S1°W, 30.0' 18" Oak S68°E, 42.2'
1/2" iron pipe & Cedar post found in place 7" Double Maple S46°W, 29.1' 26" W Pine N68°W, 67.7'
6" iron pipe in center-line of road found in place 6" Oak N78°W, 52.7' 6" J Pine S55°E, 25.7'

CURVE DATA
Radius = 30.00'
Central Angle = 80°12'16"
Arc Length = 42.04'
Chord Bearing & Length = N39°56'08"W 38.68'

NOTE
Lot 6-A may not comply with Chapter H-65 of the Wisconsin Administrative Code and is intended to be sold to the purchaser of Lot 6

DETAIL
Scale 1"=100'

LEGEND
- 1 1/2" iron pipe found in place
- 2" iron pipe found in place
- 1" x 30" Round iron pipe set, weighing 1.13 pounds per lineal foot
- 2" x 30" Round iron pipe set, weighing 3.65 pounds per lineal foot
- Existing building

NOTE
Legal descriptions have been provided on separate sheets

RECEIVED & FILED # ~~D6116~~
Oneida County Surveyor's Office
Date 4 Nov. 80
By D.W. Winant
OCS Area # 192-18-3848

Drawn by B L Rindt
1&2-18-388